STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	0	0	0	0

RECAPITULATION OF SIGNING & DELINEATION BID ITEMS

BID ITEMS	APPROXIMATE QUANTITIES		UNITS
SIGN (FLAT SHEET) (HIGH PERFORMANCE)			SQUARE FOOT
SIGN (REINFORCED PANEL) (HIGH PERFORMANCE)			SQUARE FOOT
SIGN (OVERLAY) (HIGH PERFORMANCE)			SQUARE FOOT
SIGN POST (4" x 6" WOOD) (FLAT SHEET SIGN)			LINEAR FOOT
SIGN POST (4" x 6" WOOD) (REINFORCED PANEL SIGN)			LINEAR FOOT
SIGN POST (2 LB/FT "U" STEEL)			LINEAR FOOT
SIGN POST (3 LB/FT "U" STEEL)			LINEAR FOOT
SIGN POST (1-3/4" PERFORATED SQUARE STEEL TUBE)			LINEAR FOOT
SIGN POST (2" PERFORATED SQUARE STEEL TUBE)			LINEAR FOOT
SIGN POST (2-1/4" PERFORATED SQUARE STEEL TUBE)			LINEAR FOOT
SIGN POST (2-1/2" PERFORATED SQUARE STEEL TUBE)			LINEAR FOOT
SIGN POST (4" X 6" STRUCTURAL STEEL)			LINEAR FOOT
SIGN POST (3 I 2.25 ALUMINUM)			LINEAR FOOT
	A36	A572(ALT)	
SIGN POST (W6X9 STEEL BEAM)			LINEAR FOOT
SIGN POST (W10X12 STEEL BEAM)			LINEAR FOOT
SIGN POST (W10X22 STEEL BEAM)			LINEAR FOOT
SIGN POST STUB WITH BREAKAWAY BASE PLATE (W6X9)			EACH
SIGN POST STUB WITH BREAKAWAY BASE PLATE (W10X12)			EACH
SIGN POST STUB WITH BREAKAWAY BASE PLATE (W10X22)			EACH
SIGN POST BREAKAWAY BASE PLATE (W6X9)			EACH
SIGN POST BREAKAWAY BASE PLATE (W10X12)			EACH
SIGN POST BREAKAWAY BASE PLATE (W10X22)			EACH
SIGN POST FOOTING (24" Dia. CONCRETE)(STEEL BEAM POST)			LINEAR FOOT
SIGN POST FOOTING (30" Dia. CONCRETE)(STEEL BEAM POST)			LINEAR FOOT
SIGN POST FOOTING (18" Dia. CONCRETE)(WOOD POST)			LINEAR FOOT
SIGN POST FOOTING (1-3/4" PERFORATED SQUARE STEEL TUBE)			EACH
SIGN POST FOOTING (2" PERFORATED SQUARE STEEL TUBE)			EACH
SIGN POST FOOTING (2-1/4" PERFORATED SQUARE STEEL TUBE)			EACH
SIGN POST FOOTING (2-1/2" PERFORATED SQUARE STEEL TUBE)			EACH
SIGNING OBJECT MARKER (TYPE 2)			EACH
SIGNING OBJECT MARKER (TYPE 3)			EACH
SIGNING DELINEATOR (TYPE A)(WHITE RIGID, "U" POST)			EACH
SIGNING DELINEATOR (TYPE A)(YELLOW RIGID, "U" POST)			EACH
SIGNING DELINEATOR (TYPE B)(WHITE RIGID, "U" POST)			EACH
SIGNING DELINEATOR (TYPE B)(YELLOW RIGID, "U" POST)			EACH
SIGNING DELINEATOR (TYPE A)(WHITE FLEXIBLE)(TYPE I ANCHOR)			EACH
SIGNING DELINEATOR (TYPE A)(YELLOW FLEXIBLE)(TYPE I ANCHOR)			EACH
SIGNING DELINEATOR (TYPE B)(WHITE FLEXIBLE)(TYPE I ANCHOR)			EACH
SIGNING DELINEATOR (TYPE B)(YELLOW FLEXIBLE)(TYPE I ANCHOR)			EACH
SIGNING DELINEATOR (TYPE A)(WHITE FLEXIBLE)(TYPE 3 ANCHOR)			EACH
SIGNING DELINEATOR (TYPE A)(YELLOW FLEXIBLE)(TYPE 3 ANCHOR)			EACH
SIGNING DELINEATOR (TYPE B)(WHITE FLEXIBLE)(TYPE 3 ANCHOR)			EACH
SIGNING DELINEATOR (TYPE B)(YELLOW FLEXIBLE)(TYPE 3 ANCHOR)			EACH

BID ITEMS	APPROXIMATE QUANTITIES	UNITS

Note:
The contract bid for steel beam posts, stub posts, base plates, and footings will be based on A36 Grade steel quantities. When furnishing the A572 Grade alternate steel, the payment will be based on the equivalent A36 steel unit prices in the contract.

NO.	DATE	REVISIONS	BY	APP'D
02	10-01-19	Removed PSST coupler and changed the tables	D.D.G.	E.W.N.
01	07-23-10	Changed Bid Items as per Spec Book (2007)	D.D.G.	D.B.

KANSAS DEPARTMENT OF TRANSPORTATION

RECAPITULATION OF SIGNING & DELINEATION BID ITEMS

TE450 07-01-03

FHWA APPROVAL		10-01-19	APP'D.	Steven A. Buckley	
DESIGNED	D.D.G.	DETAILED	K.D.S.	QUANTITIES	TRACED
DESIGN CK.	S.A.B.	DETAIL CK.	D.D.G.	QUAN.CK.	TRACE CK.

KDOT Graphics Certified 05-26-2022 Sh. No. 0

KDOT Graphics Certified

Plotted by : KDOT#CADD.Support_ks.gov 7-OCT-2022 21:35
File : te450.dgn